

Project Planning Considerations For Emerging Contaminants

Ed Corl NAVSEA LQAO

maintaining the data needed, and c including suggestions for reducing	lection of information is estimated to ompleting and reviewing the collect this burden, to Washington Headquuld be aware that notwithstanding an DMB control number.	ion of information. Send comments arters Services, Directorate for Infor	regarding this burden estimate of mation Operations and Reports	or any other aspect of th , 1215 Jefferson Davis I	is collection of information, Highway, Suite 1204, Arlington	
1. REPORT DATE MAR 2012		2. REPORT TYPE		3. DATES COVERED 00-00-2012 to 00-00-2012		
4. TITLE AND SUBTITLE			5a. CONTRACT	NUMBER		
Project Planning C	Considerations For E	5b. GRANT NUM	IBER .			
		5c. PROGRAM E	LEMENT NUMBER			
6. AUTHOR(S)		5d. PROJECT NU	MBER			
				5e. TASK NUMB	ER	
				5f. WORK UNIT	NUMBER	
Naval Sea Systems	ZATION NAME(S) AND AE Command (NAVSE ce (LQAO) ,1333 Isa 576	EA),Laboratory Qua	•	8. PERFORMING REPORT NUMBI	GORGANIZATION ER	
9. SPONSORING/MONITO	RING AGENCY NAME(S) A	ND ADDRESS(ES)		10. SPONSOR/MONITOR'S ACRONYM(S)		
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)		
12. DISTRIBUTION/AVAIL Approved for publ	LABILITY STATEMENT ic release; distributi	on unlimited				
13. SUPPLEMENTARY NO Presented at the 9t 26-29 March 2012	h Annual DoD Envi	ronmental Monitori	ing and Data Qua	ality (EDMQ)) Workshop Held	
14. ABSTRACT						
15. SUBJECT TERMS						
16. SECURITY CLASSIFICATION OF: 17. LI				18. NUMBER	19a. NAME OF	
a. REPORT unclassified	b. ABSTRACT c. THIS PAGE San Report			OF PAGES 29	RESPONSIBLE PERSON	

Report Documentation Page


Form Approved OMB No. 0704-0188

Overview

- Primary Problems
- Current ELAP status on EC's
- Early Planning Considerations
- Recommendations for Project Managers & Labs

Major Hurdles

- No methods exist for the parameter(s) of interest
- No IRIS values exist/interim values
- Lower risk-based values are beyond quantification capabilities of the current method(s)
- No ELAP accredited labs exist for the parameter(s) of interest
- No standards exist for the parameters(s) of interest



Early Sensitivity Issues

Detection Limits

"The analytical data objective for baseline risk assessments is that the uncertainty is known and acceptable, not that the uncertainty be reduced to a particular level."

"Whenever possible, methods should not be used if the detection limits are above the relevant concentrations of concern. The MDL should be no greater than 20% of the concentration of concern."

"To protect human health, place a higher priority on preventing false negatives in sampling and analysis than on preventing false positives."

Guidance for Data Usability in Risk Assessment, EPA Office of Emergency and Remedial Response, April 1992.

Detection Limits, Cont.

NCP 40 CFR 300.430(e)(2)(i): "Remediation goals shall be developed considering...technical limitations such as detection/quantification limits..."

RAGs, Part A, section 5.3.4 "....SQLs are the most appropriate limits to consider when evaluating non-detected chemicals"

".....reported concentration (i.e., data that are not "tentative," "uncertain," or "qualitative") are appropriate for use in the quantitative risk assessment.

Current ELAP Status for C6+6

MATRIX	METHOD	DoD ELAP Labs	Screening Level	LOD	LOQ
Soil	SM 3500CR C	0	0.29 mg/kg	0.05 - 0.16	0.1 - 2.0
Soil	SW 846 7199	1	0.29 mg/kg	0.0596	0.60
Soil	SW 846 7195	1	0.29 mg/kg	140	1300
Soil	SW 846 7196	45	0.29 mg/kg	0.16 - 2.392	0.2 - 10.0

Current ELAP Status for C6⁺⁶, Cont.-

		9		
METHOD	Labs	Level	LOD	LOQ
SM 3500CR C	0	0.031 ug/L	0.015 - 5.0	5.0 - 10.0
SW 846 7199	1	0.031 ug/L	0.18	0.50
SW 846 7195	1	0.031 ug/L	6.6	25
SW 846 7196	50		0.01 - 25	0.02 - 60.0
				0.10 μg/filter
011 040 7 130		o.oooorr ag/iii		
CIM OAE EDOO				0.5 μg/L
	4			(QL), 0.0125 mg/kg (QL)
	SW 846 7199	METHOD Labs SM 3500CR C 0 SW 846 7199 1 SW 846 7195 1 SW 846 7196 50 SW 846 7196 0 SW 846 6800 0	METHOD Labs Level SM 3500CR C 0 0.031 ug/L SW 846 7199 1 0.031 ug/L SW 846 7195 1 0.031 ug/L SW 846 7196 50 0.031 ug/L SW 846 7196 0 0.000011 ug/m³ SW 846 6800 0 0.000011 ug/m³	METHOD Labs Level LOD SM 3500CR C 0 0.031 ug/L 0.015 - 5.0 SW 846 7199 1 0.031 ug/L 0.18 SW 846 7195 1 0.031 ug/L 6.6 SW 846 7196 50 0.031 ug/L 0.01 - 25 SW 846 7196 0 0.000011 ug/m³ SW 846 6800 0 0.000011 ug/m³

Current ELAP Status for TCE

MATRIX	METHOD	DoD ELAP Labs	Screening Level	LOD	LOQ
IVIZATION	III III III III III III III III III II	Lubo	20701		200
Soil	SW 846 8260	65	0.91 mg/kg	0.000187 - 1	0.001 - 5
Soil	EPA 624	0	0.91 mg/kg	0.000187 - 1	0.001 - 5
Water	SW 846 8260	65	0.44 μg/L	0.1 - 2.5	0.5 - 5
Water	EPA 624	24	0.44 μg/L	0.1 - 2.5	0.5 - 5
Water	SW 846 8260SIM	2	0.44 μg/L	0.025	0.05
Water	020001111	_	OITT MS/L	0.020	0.00
Water	EPA 524.2	11	0.44 µg/L	0.25	0.5
Air	EPA TO-15	21	0.43 μg/m³	0.11 - 2.69	0.21 - 2.7

Current ELAP Status for 1,4-Dioxane

MATDIV	METHOD	DoD ELAP	Screening	LOD	1.00
MATRIX	METHOD	Labs	Level	LOD	LOQ
Soil	SW 846 8270	16	4.9 mg/kg	0.0234 - 0.33	0.0667 - 0.33
Soil	EPA 625	2	4.9 mg/kg	0.0234 - 0.33	0.0667 - 0.33
Soil	SW 846 8270SIM	2	4.9 mg/kg	0.01 - 0.05	0.02 - 0.1
Soil	SW 846 8260	35	4.9 mg/kg	0.025 - 0.25	0.05 - 1
Water	SW 846 8270 Modified	1	0.67 μg/L	0.25	1.0
Water	SW 846 8270	16	0.67 µg/L	0.324 - 10	1.0 - 10

ELAP Status for 1,4-Dioxane, cont.-

MATRIX	METHOD	DoD ELAP Labs	Screening Level	LOD	LOQ
Water	EPA 624	6	0.67 μg/L	0.324 - 10	1.0 - 10
Water	SW 846 8270SIM	2	0.67 μg/L	0.4 - 1	1 - 3
Water	SW 846 8260	35	0.67 μg/L	1.5 - 320	3 - 1000
Water	SW 846 8260SIM	4	0.67 μg/L	1	2
Air	EPA TO-15	13	0.49 μg/m³	0.18 - 1.8	0.36 - 7.2
Tissue	SW 846 8270	1		0.1 mg/kg	0.1 mg/kg

Current ELAP Status for B(a)P

	i			<u> </u>	
MATRIX	Method	DoD ELAP Labs	Screening Level	LOD	LOQ
Soil	SW 846 8270	66	0.015 mg/kg	0.0004 - 0.625	0.005 - 0.66
Soil	EPA 625	0	0.015 mg/kg	0.0004 - 0.625	0.005 - 0.66
Soil	SW 846 8270 SIM	2	0.015 mg/kg	0.001 - 0.02	0.001 - 0.1
Soil	SW 846 8310	19	0.015 mg/kg	0.0001 - 0.0076	0.005 - 0.01
Water	SW 846 8270	65		0.05 - 10 ug/L	0.2 - 20 μg/L
Water	EPA 625	27		0.05 - 10 μg/L	0.2 - 20 μg/L


ELAP Status for B(a)P, Cont.-

		DoD			
		ELAP	Screening		
MATRIX	Method	Labs	Level	LOD	LOQ
	SW 846 8270			0.005 - 0.1	0.02 - 0.2
Water	SIM	4		μg/L	μg/L
				0.007 - 0.066	0.1 - 0.2
Water	SW 846 8310	18		μg/L	μg/L
				2.0 - 5.0	2.0 - 5.0
Air	SW 846 8270	0		μg/PUF	μg/PUF
				2.0 - 5.0	2.0 - 5.0
Air	EPA TO-13	3		μg/PUF	μg/PUF
					0.0005
Tissue	SW 846 8260	1		0.0002 mg/kg	mg/kg
				0.0234 - 0.1	0.1 - 0.4
Tissue	SW 846 8270	2		mg/kg	mg/kg

Additional PAHs from 2010 RPF Assessment

- Anthanthrene
- Benzo[g,h,i]perylene
- Benzo[j]fluoranthene
- Cyclopenta[c,d]pyrene
- Dibenzo[a,e]fluoranthene
- Dibenzo[a,e]pyrene
- Dibenzo[a,h]pyrene
- Dibenzo[a,i]pyrene
- Dibenzo[a,l]pyrene
- Fluoranthene

- Benz[b,c]aceanthrylene
- Benz[e]aceanthrylene
- Benz[j]aceanthrylene
- Benz[l]aceanthrylene
- Cyclopenta[d,e,f]chrysene
- Naphtho[2,3-e]pyrene





- No Calibration Standards with appropriate pedigree currently exist for some.
- SW 846 8270 SIM will likely be sufficient for quantification

Dioxin State Soil Cleanup Levels

State	Unrestricted/ Residential (ppt)	Commercial/ Industrial (ppt)	Target Cancer Risk Level	Terminology for Level
FL	7	30	10E-06	Soil cleanup target level for TCDD TEQ
GM	450	1,800	10E-04	Action level for dioxin TEQ
н	390	1,600	10E-04	Action level for dioxin TEQ
ME	10	30	10E-06	Generic soil cleanup level for dioxin TEQ
NH	9	300	10E-06	Risk-based soil standard for TCDD
WA	11		10E-06	Cleanup level for TCDD

Source: USEPA. 2009. Review of State Soil Cleanup Levels for Dioxin. National Center for Environmental Assessment, Washington, DC. December. Available from http://www.epa.gov/ncea.

Additional Dioxin Levels - California

May 2009 HHRA Note #2

- -http://www.dtsc.ca.gov/assessingrisk/humanrisk2.cfm
- –PRG based on TCDD TEQ
 - •Residential = 50 ppt residential,
 - Commercial/Industrial = 200-1000 ppt
 - •Agricultural = <40 ppt
- -Lesson learned to other states—don't assume there are just residential values...check!

Current ELAP Status for Dioxin

	<u> </u>				
MATRIX	METHOD	DoD ELAP Labs	Screening Level	LOD	LOQ
Soil	SW 846 8280	0	4.5 x 10 ⁻⁷ mg/kg	2.5 x 10 ⁻⁴	5 x 10 ⁻⁴
Soil	SW 846 8290	12	4.5 x 10 ⁻⁷ mg/kg	1 x 10 ⁻⁷ – 1 x 10 ⁻⁴	1 x 10 ⁻⁶ – 1 x 10 ⁻³
Soil	SW 846 1613/ SW 846 8290	8	4.5 x 10 ⁻⁷ mg/kg	3.4 x 10 ⁻⁷	1 x 10 ⁻⁶
Water	SW 846 8280	1	5.2 x 10 ⁻⁷ ug/L	2.5 x 10 ⁻³	5 x 10 ⁻³
Water	SW 846 8290	12	5.2 x 10 ⁻⁷ ug/L	2 x 10 ⁻⁶ – 6.67 x 10 ⁻⁶	1 x 10 ⁻⁵ – 1 x 10 ⁻⁴

ELAP Status for Dioxin, Cont.-

MATRIX	METHOD	DoD ELAP Labs	Screening Level	LOD	LOQ
Water	SW 846 1613/ SW 846 8290	9	5.2 x 10 ⁻⁷ ug/L	0.002	0.01
Tissue	SW 846 8290	0		1.5 x 10 ⁻⁷ – 1 x 10 ⁻⁴	5 x 10 ⁻⁶ – 1 x 10 ⁻³
Ticcuo	SW 846 1613B/ SW 846 8290	0		2 x 10 ⁻⁷	1 x 10 ⁻⁶
Tissue Tissue	EPA 1613B	1		2 x 10 ⁻⁷	5 x 10 ⁻⁷
Air			6.4 x 10 ⁻⁸ ug/m ³		

Dioxin Toolkit

Uniform Federal Policy

Quality Assurance Project Plan

for

Soils Reassessment of Dioxin Sites

[Insert FORMER NPL or OTHER REMEDIATED SITE NAME]

[Insert Site LOCATION and STATE]

[Insert DATE]

- •2010- Prepared by the U.S Environmental Protection Agency (EPA) Office of Superfund Remediation and Technology Innovation (OSRTI)
- Includes UFP-QAPP worksheet templates and Users guide
- Utilizes Incremental Sampling Approach
- Addresses issues regarding:
 - sensitivity requirements
 - uncertainty

Dioxin Reassessment Guide

- Review Historical Data
- Suggest optimal sampling and analytical strategies
- Develop appropriate size, shape, and orientation of reassessment decision units (DUs)
- Determination of constituent background concentrations (1-11 ppt?)
- Substitute for, or augment, current data collection needs
- Perform TEQ-based risk screening by evaluating the total TEQ against the interim Preliminary Remediation Goal (PRG)

Historical Data

- Were quantitation limits sufficient?
- Did data quality indicators meet method performance requirements?
- Demonstration of method applicability (DMA) to establish the comparability between conventional and alternative methods?
- Did any of the historical analytical methods find matrix interferences that warrant consideration when selecting extract cleanup methods for future analyses?
- Are there QC or validation records available?
- Use previous data to help with future events

Dioxin TEQ Considerations

- How will qualified data be used in TEQ calculations?
- How will co-elutions be treated?
- How will non-detects be used?
- How will blank results be used?
- Sampling-containers/solvents certified down to appropriate level
- Clean sampling procedures?
- Document in QAPP

Considerations for Project Chemists

- Defaulting to QSM limits may not be appropriate:
 - "Method Blanks- Use project-specific criteria, if available. Otherwise, no analytes detected ≥ LOD for the analyte or ≥ 5% of the associated regulatory limit for the analyte or ≥ 5% of the sample result for the analyte, whichever is greater, per method."
 - "LCS- project-specific criteria, if available. Otherwise, use inhouse control limits. In-house control limits may not be greater than ± 3 times the standard deviation of the mean LCS recovery."

Options for the Lab

- Modify existing method
 - > Pre-concentration
 - >Additional clean-up
 - Different wavelength or mass
 - Different Sample mass
 - Standard Addition
- Use an alternative method
 - > isotope dilution

Considerations for Project Managers

- Is the EC the only COC driving the risk?
- Does the CSM suggest that EC might be present?
- Background Concentrations
- Risk Management (risk range for carcinogens)
- Alternative risk-based values
- Don't sample until:
 - -Early planning with the risk assessor, chemist, & lab
 - -Work with regulator to plan for data of known quality

Considerations for Project Managers

- Project team should work with project chemist and risk assessor to select a PAL, method, and lab that can achieve objectives with data of known confidence.
- Document objectives, methods, MPC's in a QAPP prior to sampling

Options for Project Managers

- When PAL is firm and no existing DoD ELAP lab is available :
- 1. Project team should first approach lab to expand their scope of accreditation.
- 2. Lab contacts AB to coordinate.

Options for Project Managers

- When PAL is firm, identified lab is not accredited and is NOT requesting formal DoD accreditation:
- 1. Project manager contacts DoD EDQW principal (I
- 2. DoD EDQW principal will review QAPP and the identified lab's capabilities for a project-specific approval through EDQW.
- 3. Scope of review, level of effort, and practicability of the project-specific approval is subject to EDQW.

Options for Project Managers

- When PAL is firm and no lab has been identified:
- 1. Project manager contacts DoD EDQW principal to assist in options.
- 2. DoD EDQW principal will review QAPP and assist in identifying candidate labs.
- 3. The EDQW should only be involved as a last resort. Project-specific reviews/approvals will be considered on a limited basis.